STERLING

Burdon Way
Stokesley Business Park
Stokesley, North Yorkshire
TS9 5PY

T 01642 713333
E sales@sterlinggp.com
W www.sterlinggp.com

PROPOSAL & QUOTATION

Quantity	Description
1.00	Supermix 8 drum manufactured from 5mm S355 steel. Air volume of 16m³ with standard flush fit access hatch and additional large access hatch. Superior helical coil geometry and capped blades to ensure quality mix of concreteSuperfast charge and discharge rates for large-scale projects
1.00	Mixer frame to suit free issue 32T 8x4 Chassis Cab with Live drive engine PTO and day cabHeavy duty steel rear rollers with premium brand case hardened bearings. Rollers and track ring can be greased from ground level via remote greasing point manifold.
1.00	3mm S355 steel main swivelling pan chute, with handles to both sides. 'Helicopter' lock to secure position and 'telescope' screw jack to adjust height2 additional extension chutes supplied with stowage to offside of truck
1.00	Full height loading hopper set to 40 Degrees to allow loading concrete from a wet or dry batching plant. Nominal 12ft loading height
1.00	PTO Propshaft with 100mm DIN flange connected to live drive PTO. PMP axion piston 90cc pump connected to 90cc motor driving through PMP 6.5 Gearbox (120.3:1)
1.00	ASA Oil Cooler and reservoir fitted to hydraulic circuit with temperature switch set to 60°C to maintain correct operating temperature
1.00	Mixer drum speed controlled by manual lever controls to rear control station and second lever in cabEngine speed controlled by switch to rear control station with in cab activation button
1.00	350L plastic water tank positioned over gearbox

STERLING

Burdon Way
Stokesley Business Park
Stokesley, North Yorkshire
TS9 5PY

T 01642 713333
E sales@sterlinggp.com
W www.sterlinggp.com

1.00	Water system with centrifugal pump powered by gearbox PTO connected to wash down hoses to platform and rear of truck. Water supply into drum through flowmeter
1.00	Awaywash tray fitted to rear of mixer to allow washing down without discharging water on site
1.00	White conspicuity tape fitted to sides of truck to meet legal requirements and red across rear
1.00	LED worklights fitted to rear of truck and under water tank
1.00	LED Strobe lights fitted to rear of mixer
1.00	Drum Anti-Creep securing kit
1.00	Mixer frame shot-blasted and painted to customers colour choice in 2 pack paint single colour
1.00	Mixer drum shot-blasted and painted to customers colour choice in 2 pack paint single colour
1.00	Type Approval for completed Mixer

WE REQUIRE FULL PAYMENT PRIOR TO THE RELEASE OF THE VEHICLE FROM STERLING GP LTD. ALL QUOTES ARE VALID FOR 30 DAYS. E+OE. WE RESERVE THE RIGHT TO CHARGE INTEREST ON OVERDUE ACCOUNTS AT THE RATE OF 5% OVER THE BANK OF ENGLAND BASE RATE

Terms and Conditions

ALL TRANSACTIONS ARE TO BE CONDUCTED IN ACCORDANCE WITH THE TERMS AND CONDITIONS FOUND AT WWW.STERLINGGP.COM/TERMS-CONDITIONS/.

WE REQUIRE FULL PAYMENT PRIOR TO THE RELEASE OF THE VEHICLE FROM STERLING GP LTD. ALL QUOTES ARE VALID FOR 30 DAYS. E+OE.

DUE TO UNPRECEDENTED COST INCREASES EXPERIENCED THIS YEAR, WE RESERVE THE RIGHT TO AMEND THE PRICE DETAILED IN THIS QUOTATION UP TO BUT NO LATER THAN 6 MONTHS PRIOR TO THE BUILD COMMENCING. THE PRICE WILL BE GUARANTEED FROM THIS POINT ONWARDS. THIS CLAUSE WILL ONLY APPLY IF COSTS INCREASE FURTHER THAN ALREADY BUDGETED.

S007 Document Created 07/05/2026