

Technical specification HIAB 21-ton hooklift

HIAB 21 ton hooklift model ULT 21SL53 – D - OCF

Low-built hooklift with telescopic sliding hook arm

Build height 195 mm

Capacity 21 tons

Hydraulic body locks

Removable hook

Control system PLC second generation control unit

Stainless tank 155 liters incl. shut-off valve to suction connection

Side control of hook during tipping

Control unit on handle at A-pillar

Emergency stop in cab

Electric function with hook arm front/rear. Sliding/tilting

Operating meter

Spreader tailgate opener

Valve placement – Mounted in equipment bracket

Hydraulic oil – Mineral oil

Body support 1

Emergency drive key

Extra functions. Hook arm front/rear. Sliding/Tilting

Friction reduction

Automatic sequence

High-speed operation

Fast tipping

Fast lowering

External warning buzzer

Control of trailer tipping

Lift cylinder pressure limitation when maneuvering to trailer

Safespeed, end-of-movement damping

Proportional control

VBG 795 air-controlled coupling
Reversing camera 2 pcs mounted rear on vehicle, one central and one on left rear fender
Camera preparation for trailer rear in frame
Strobe light bar on roof and 2 pcs rotating lights rear
Strobe lights rear
Work lighting, 2 at step, 4 pcs behind cab on hooklift frame and 2 pcs furthest rear
Plastic fenders
Pressure and return rear to trailer
Duo-matic rear to automatic tailgate
Stainless side covering left side
Toolboxes 3 pcs covering right side
Equipment bracket for shovel and brush